

32 00 00 Exterior Improvements**32 01 00 Operations and Maintenance of Exterior Improvements:**

1. Existing plant material to be retained, including plants that may be affected by construction activities both within and outside the actual project limits, shall meet the protection and maintenance requirements specified in this section. Such plant and root systems shall be protected from damage, compaction and contamination resulting from construction.
2. All deciduous trees within the work zone shall be protected with wood plank tree protection. Maintain tree protection during construction period. Remove only when risk of damage has passed and upon approval by the University's representative.
3. Tree protection shall be 28 x 89 mm wood planks, minimum 1500 mm long, secured with two bands of metal strapping. Place wood planks around base of trunk at 150 mm maximum on center to provide full protection from impact and abrasion. Do not puncture or damage bark with wood planks or fasteners. Arrange wood planks around branches and other irregularities to provide protection without damaging tree.
4. Prevent damage to trees and shrubs in lawn areas or planting beds that are to remain by erecting a snow fence barrier to provide a continuous barricade between designated plant materials and the work area prior to construction. Place snow fence at dripline of trees unless inadequate to provide a 1.5 m buffer zone between the fence and limit of construction. Dripline is defined as ground surface directly beneath tips of outermost branches, at least 3 m radius from the tree trunk or larger as directed by the University's representative. With the permission of the University's representative, the fence may be placed within dripline of tree to provide a buffer zone of up to 1.5 m, but in no case less than 1 m from the outer circumference of the trunk.
5. Do not operate, park, repair or refuel equipment, do not store construction materials, or stockpile any earth materials within barricades or within 2 m of the outer edge of the drip line of a tree. Do not cause flooding or deposition of sediment where trees are located. Maintain barricades during construction operations and remove on completion as directed by the University's representative.
6. Snow fence barrier shall be standard plastic fencing or approved equivalent in good condition, 1.2 m high, supported vertically by steel T-bars, and horizontally at the top of the fencing by 39 x 89 mm wood railing, bolted to the steel T-bars. T-bars are to be straight, 1.8 m long. Drive T-bars vertically 60 cm into ground, spaced maximum 4.5 m apart. Wire snow fence at 3 places to each T-bar. Stretch snow fence to prevent sag.

32 05 00 Common Work Results for Exterior Improvements:

1. Landscaping may be included in the building contract. Landscape design shall be reviewed by the Campus Grounds Advisory Committee (CGAC) and approved by the Campus Planning and Development Committee (CPDC).

32 10 00 Paving:

1. Low Impact Development (LID) technology, such as permeable pavement, shall be the

32 00 00 Exterior Improvements

Queen's University Building Design Standards

primary material used. Any other option shall be at the approval of Queen's Facilities.

2. Parking lots must adhere to the City of Kingston's Zoning Bylaw, section 7.
3. Parking lots shall include at least the minimum number and type of accessible parking spaces according to the Queen's Facility Accessibility Design Standards.
4. Tree and shrub plantings must be incorporated within and around parking lots, in an arrangement that adequately provides shade to at least 50% of parking spaces when trees are mature. See Appendix E for an example.
 - a. This standard shall apply to new, existing and renovated parking lots.
 - i. Tree plantings shall be planted inside curbed, soil filled planting area's that shall have a minimum inside dimension of 3.05m.
 - ii. The soil depth within the planting shall be at least 1.5 meters.
 - iii. The tree(s) must be planted away from, and accounting for, power lines.
 - iv. Planting mixture and installation requirements from division 32 93 00 Plants, shall be complied with.
 - b. Submissions must include a project proposal with statements responding to the following considerations.
 - c. Careful consideration must be taken when choosing the species of the tree(s)
 - i. The tree(s) must not reach a height of >25m (WV Division of Forestry Urban & Community Forestry, 2020).
 - ii. The species should be resilient to the specific climate conditions of the area.
 - iii. The species should be resistant to diseases/pests.
 - iv. The species should not bear fruit that may cause a displeasing environment.
 - d. Other considerations include:
 - i. Ensure the soil is deep enough to sustain the root system of a mature tree(s).
 - ii. Ensure there are appropriate barriers in place to protect the tree(s) from snow clearing operations and general traffic.
 - iii. To reduce lawn maintenance requirements, utilize small plantings in the understory.
 - iv. To manage rainfall and run off, the implementation of rain gardens is preferred.
 - e. Soil Cell infrastructure beneath the trees and plantings shall be the primary option for below surface support. Any other option shall be at the approval of Queen's Facilities.

32 14 00 Unit Paving:

1. Unit paving should be unified by set dimensions and colours for field paving, borders, banding, and accents. Variety can be achieved by varying the pattern at specific locations in response to the setting. The perimeter of unit paving areas should be defined by walls, curbs, and paver edging system and banding material, as appropriate for the location. Unit paver for field paving shall be 200 x 200 mm size in dark grey colour, and for borders and banding shall be 100 x 100 mm grid size, textured, natural (light grey) colour. Pavers shall be laid in stack bond pattern, flush with adjacent paving. The standard widths for unit paver border and banding shall be 600 mm and 400 mm respectively. The University shall approve paver size, colour and pattern for non-standard field, banding, and accents.

32 00 00 Exterior Improvements

Queen's University Building Design Standards

2. Unit pavers approved for use at walkways shall be of colour and pattern consistent with the predominant precedent in the streetscape and vicinity. Finish and detailing should be durable, attractive, low maintenance, slip resistant, wheelchair accessible and convenient for snow removal.

32 16 00 Concrete Walks and Curbs

32 16 13 Curbs:

1. Concrete curbs at sidewalks shall be flush with sidewalk. Concrete curbs defining shrub beds and turf areas shall be raised a minimum of 100 mm above finish grade of adjacent paving.
2. Exposed edges of concrete curbs shall be rounded or chamfered to prevent chipping and damage from maintenance equipment. Sharp edges and corners shall be avoided.
3. The dimension, finish and detailing of concrete curbs should be compatible with the predominant precedent in the vicinity, and should be durable, attractive, and low maintenance.
4. Curbs adjacent to hard surfaces shall be fitted with skateboard deterrent devices that are tamper-proof, safe, attractive, designed to minimize liability and blend in with the character of the site.

32 16 23 Sidewalks:

1. Walkway construction in a project should take into consideration the specific character of the site and the campus precinct, recognize the unique purpose of the project, ensure the continuity of design in the pedestrian circulation network, and effect economies in the long-term maintenance of that network. Walkway layout and dimension should follow desired line of pedestrian movement and adequately accommodate pedestrian traffic. Walkway detailing should signify pedestrian priority, indicate changes in use (e.g., city sidewalk, sidewalk widening, transition space and linkages), and provide clear separation between pedestrians and vehicles at high use zones.
2. Major sidewalk shall be poured-in-place concrete. Width shall be 3-3.5m and may be modified if justified by use and site conditions. Where city sidewalks need to be widened to accommodate pedestrian needs, sidewalk widening of 1 m or wider than the standard city sidewalk shall have a unit paver border at the back of the city sidewalk. The standard unit paver border shall be 600 mm wide, unless approved by the University. Unit paver shall be 100 x 100 mm grid size, textured, natural (light grey) colour, laid in stack bond pattern, flush with adjacent paving.
3. Standard sidewalk shall be poured-in-place concrete, natural (light grey) colour, 2-2.5m wide. Standard unit paver border at the back of the curb shall be determined on a project-by-project basis, depending on local conditions.
4. Major walkways shall be 3m to 3.5m wide. Standard walkways shall be 2-2.5m wide. Major and standard walkways shall be poured-in-place concrete, natural (light grey) colour, with unit paver border along both edges. The width of the border shall be approximately 750 mm (5 courses) wide for walkways 3 m or wider, and approximately 450 mm (3 courses) wide for walkways less than 3 m wide. The University shall approve variances in border width that are required to suit site and walkway proportion. Border shall be tumbled concrete unit paver 150 x 150 mm size, dark grey colour, laid in stack bond pattern.

Last Updated: August 18, 2025

32 00 00 Exterior Improvements

Queen's University Building Design Standards

Walkway and border surfaces should finish flush.

5. Minor walkway shall be 1.6-1.8 m wide poured-in-place concrete, natural (light grey) colour. If a minor walkway is not the sole accessible route to a facility, alternate materials may be accepted subject to the University's approval. Alternate materials should be durable, attractive, low maintenance, slip resistant, wheelchair accessible and convenient for snow removal.
6. Shared Streets intended for multimodal travel and vehicle use shall be poured-in-place concrete, 4-4.5m wide.
7. Walkways restricting vehicle use shall be clearly distinguishable through design. Examples include distinction in materials, edge treatments, and barriers to pathway entry points that deter vehicle entry.
8. Concrete walkway configuration, finish and detailing should be compatible with the established design on campus, be appropriate for the intended use and maintenance equipment, and should be durable, attractive, low maintenance, slip resistant, wheelchair accessible and convenient for snow removal. Concrete shall be broom finish, in straight lines perpendicular to the primary direction of travel. Paving patterns may be adapted in response to setting but should ensure continuity with the established walkway design on campus. Unnecessary grade changes and steps should be avoided, and if present, alternate, and convenient accessible routes should be provided.
9. Patios and courts along major pedestrian routes shall be poured-in-place concrete to provide ease of wheelchair access. Field paving materials other than poured-in-place concrete is subject to university approval. The use of unit pavers shall be limited to borders, banding, and accents.
10. Poured-in-place concrete shall meet the appearance and performance criteria specified in these standards. Unit paver for border and banding shall be 100 x100 grid size, textured, natural (light grey) colour, laid in stack bond pattern, flush with adjacent paving. The standard widths for unit paver border and banding shall be 600 mm and 400 mm respectively, unless approved by the University.

32 30 00 Wood Fences and Gates:

1. Wood fence should be sturdy, durable, attractive, and low maintenance.
2. Design should discourage climbing. Footing and joint detailing should minimize damage from moisture and impact from vehicles and maintenance equipment.
3. Lumber shall be pressure-treated. Colour and finish should be compatible with the site and architectural character. Apply weatherproof sealant per manufacturer's specifications.
4. Hardware should be rustproof and tamper resistant.

32 32 00 Retaining Walls

32 32 13 Cast-In-Place Concrete Retaining Walls:

1. Walls serve a variety of functions such as controlling the movement of people and vehicles, defining edges, and screening bicycles and cars. The design of walls should complement the setting and be appropriate for the intended use.
2. Poured-in-place concrete is the preferred material. Other materials are subject to the University's approval.
3. Exposed edges shall be rounded or chamfered to prevent chipping and damage from

32 00 00 Exterior Improvements

Queen's University Building Design Standards

maintenance equipment. Sharp edges and corners shall be avoided.

4. Finish and detailing should be compatible with the predominant precedent in the vicinity, and should be durable, attractive, and low maintenance. Seat wall should be minimum 400 mm wide in cross section. The standard concrete finish shall be natural (light grey) colour. Non-standard colours require University approval.
5. Walls shall be fitted with skateboard deterrent devices that are tamper-proof, safe, attractive, designed to minimize liability and blend in with the site and architectural character.

32 31 00 Metal and Chain-link Fences and Gates:

1. Fence and fittings shall be aluminum, minimum 11 gauge.
2. Minimum post size shall be 50 mm (1 7/8 in.) outside diameter. Fence post shall be direct buried in concrete footing for permanent installations.
3. Chain-link fabric shall be secured on all sides to post and frame. Maximum panel module size shall be 50 ft. wide.
4. Gate design should distribute forces evenly to avoid premature wear. Swing gate is preferred.

32 32 23 Segmental Concrete Unit Masonry Retaining Walls:

1. Retaining wall system using modular concrete units installed without mortar should be limited to areas of lower visibility and usage.
2. The colour and face texture should be grey or earth tone, depending on site and building character. Natural rock-like texture is preferred. The top of wall should be finished with cap unit. Skateboard deterrent device along top of wall and Installations should follow manufacturer's specifications.

32 33 00 Site Furnishings

32 33 13 Bicycle Racks:

1. Bicycle racks should be in well-lit and convenient locations to meet the needs of potential users. Locations that allow casual supervision from building occupants and passers-by may provide additional safeguard against theft.
2. Bicycle rack should allow the frame and one wheel to be locked to the rack with a high security, U-shaped shackle lock if both wheels are left on the bicycle.
3. Bicycle rack shall be bolted to pavement. Placement of racks should allow for parking perpendicular to the rack on both sides. A minimum clearance of 2 m between parked bicycles is required for snow removal.
4. Racks should be catalogued by item rather than custom made. The preferred product is the Ring Rack by Bikeup Bicycle Parking Systems Inc.

32 33 23 Site Trash and Litter Receptacles:

Outdoor Areas

1. See Appendix A - 32 33 23 Trash Receptacle.
2. Receptacles should be located at major activity centres and along major routes. The location of individual units should not be visually intrusive.
3. Receptacles should be durable, vandal resistant, attractive in design with easy to

Last Updated: August 18, 2025

32 00 00 Exterior Improvements

Queen's University Building Design Standards

remove liner and protection of contents from rain and weather.

4. Receptacles shall be placed in conjunction with Grounds. Receptacles shall be placed on a solid built surface and anchored in place.
5. Trash receptacle shall be production item, Victor Stanley model S-42 with S-2 spun steel dome, powder coat finish RAL 7024 graphite grey semi-gloss.

Indoor Areas

1. To enhance sorting recycling stations shall be placed, left to right, in the following order
Organics, Recycling, Paper, Garbage
2. Receptacles shall not be built into millwork.
3. Organics stream will be restricted to specific areas with high organics potential (food services areas, kitchenettes, building entrances, high traffic areas)
4. Waste stations in cafeterias and food service areas must have an organics stream.
5. All recycling stations must be production item, waste watcher XL, XL 32G/30" or 23G/30" in green, blue, grey, and black with matching signs, frames and lids with industry standard restricted container openings for each stream (Slot for paper, circle for cans, glass, plastic, wide opening for waste, and vented lift lid for organics).
6. The location of the recycling station must be visible to campus users and accommodate the function and traffic flow of the space.
7. Recycling stations shall not impede corridor widths and shall comply with the AODA's, and Ontario Fire Code's required minimum hallway width.

Washrooms

1. Waste receptacles shall be located at a convenient location for use and for ease of collection for custodial staff. The quantity of units is dependent on the size and the usage of the washroom.
2. Waste receptacle shall be production item, Rubbermaid model Vented Slim Jim 23 Gallon in Gray.

Dumpster Placement

1. Dumpster shall be placed in accordance with the Campus Master Plans guidelines on the campus look and feel
2. Dumpsters shall be accessible via a path with the minimum measurements of _x_
3. Dumpsters shall have a clearance of at minimum __

Waste Corral Specifications

1. **Enclosure**
 - a. The enclosure shall:
 - i. Be constructed of a hot dipped galvanized steel frame
 - ii. The enclosure shall have the dimensions 22'x16'5"x7'
 - iii. Be clad with 2"x6" pressure treated lumber, painted grey **OR** 24 mmx140 mm grey wood composite
 - iv. Contractor to provide pricing for both options
 - v. Have a 1/2" thick base plate
 - b. Posts shall be anchored to concrete with 1/2"x8" anchor bolts
 - c. Corner posts shall be 6"x6"x7' to secure wood framed panels
 - d. A galvanized brace shall be installed in the center of the front gates, 3"x3" angle, 30" high than 45 degrees, welded to a 6"x6" post
 - e. Brace shall attach to steel base plate that is 36"x11"

32 00 00 Exterior Improvements

Queen's University Building Design Standards

- f. Non shrink grout shall be installed under base plates as required.
 - g. The enclosure shall have two double door swing gates constructed out of 3"x3" HSS frame with 3"x3" cross brace and hinges and bolts (6'8" h x 5'-3/4" w).
 - h. The enclosure shall have a one-man door on side of structure constructed from 3"x3" HSS frame with cross brace and hinges and bolts. The door shall swing inside for pedestrian access to wheeled recycling totes, 46" x 84"
2. **Concrete Pad & Apron**
- a. Concrete pad shall be built on a gravel bed of 8" Granular A at minimum
 - i. Provide type of gravel compacted to 100% S.P.M.D.D
 - b. Finish grade shall match existing asphalt.
 - c. Pad shall be sloped at minimum ¼" per 1', back to front, away from the building.
 - d. Concrete shall be:
 - i. Exposure Class C1
 - ii. 35 Mpa at 28 days
 - e. Concrete pad shall be re-enforced by a 5/8" rebar mat embedded in the pad
 - i. Rebar shall be placed at 16" centers in each direction
 - ii. Rebar shall be supported 3" above base at pad using rebar chairs
 - f. Concrete pad shall have drilled holes drilled out to allow bolts to latch when gates are both open and closed.
 - g. Two (2) bollards shall be installed outside the enclosure at the edge of the gates when opened to 90 degrees.
 - h. Two (2) parking curbs shall be placed inside the closure behind the dumpsters at the end of construction.

32 33 43 Benches:

1. See Appendix B/C/D - 32 33 43 Benches
2. Benches should be conveniently located in areas of frequent use. A variety of seating arrangements for different social patterns and for choices in sun and shade should be provided. Seating arrangements can also help define a space.
3. Bench should be catalogued by item rather than custom made. The design should be comfortable, durable, attractive, and low maintenance.
4. Freestanding bench shall have back with no arm rests. The base plate shall be anchored to a concrete pad or footing with tamper-proof hardware.
5. Where the bench is built-in such as a seat wall, refer to Cast-in- Place Concrete Planter and Seat Walls, for requirements.
6. Free-standing bench shall be Victory Stanley model NRB-6, 6 ft. length, surface mount base, powder coat finish RAL 7024 graphite grey semi-gloss.

32 39 00 Manufactured Site Specialties

32 39 13 Bollards:

1. Rigid and collapsible bollards are used to prevent access by unauthorized vehicles to walkways and fire lanes, but do not interfere with pedestrians. A special tool allows the collapsible bollard to be lowered to the ground, remaining attached to a hinge, and then replaced in the upright position.
2. Bollards shall be Maxiforce 1 collapsible style bollard Model MF and rigid type bollard Model MF, supplied by G. Reale Enterprises, Inc., 3444 Marshall Road, Drexel Hill, PA 19026, Tel. 610-623-2611. Standard dimensions of extruded steel tubing are 6 in. x 3 in., above ground height is 32 in. Bollards shall have powder coat finish, RAL 7024 graphite

32 00 00 Exterior Improvements

Queen's University Building Design Standards

grey semi-gloss. Apply reflective tape as specified. Installation shall be per manufacturer's specifications.

32 91 00 Planting Preparation

32 91 19 Landscape Grading:

1. Subgrade preparation is required under all areas designated to receive landscaping as shown on drawings.
2. Subgrade should be free of rocks, weeds, roots, and other debris. Foreign material shall not be buried beneath areas to be landscaped.
3. Completed subgrade should be even and have positive drainage. Subgrade should be scarified to a minimum 100 mm (4 in.) depth. Subgrade shall be approved by project manager before topsoil placement begins.
4. Topsoil mixture shall be 3 parts Grade 1 topsoil, 1-part sterilized mushroom compost, 1-part peat moss. Mixture should avoid being excessively wet and should be free of weeds, roots, rocks, and other debris.
5. Place topsoil in dry weather, on dry unfrozen grade to obtain minimum depth after settlement of 100 mm (4 in.) or depth specified in planting details. Allow settling to occur for 1 week or roll to facilitate settling. Top layer should be loosely raked to allow for rooting of seed or sod. Surface should be smooth, uniform, and sufficiently firm to prevent sinkage pockets when irrigated. Surface should fall smoothly to catch basin rim and finish flush and ensure positive drainage away from building and sidewalks.
6. Project manager should be present for inspection at all stages of grading.

32 92 00 Turf and Grasses

32 92 19 Seeding:

1. Seed mixture should be 60 percent Kentucky Blue Grass, 20 percent Red Fescue, 10 percent Annual Rye, 10 percent Perennial Rye
2. Apply half of the seed at the recommended rate in a north-south direction, half in an east-west direction. Lightly rake to cover seed and roll. Water lightly and frequently until seed is established. Contractor should be responsible for two cuttings, the first at the highest level of the mower.
3. Project manager should be present for inspection at all stages of seeding.

32 92 23 Sodding:

1. Sod should be laid within 24 hours of being cut. Sod should be laid in a brick-like pattern so that joints are staggered. Cuts should be made with a sharp instrument, preferably a knife or a spade. No overlaps or gaps should be present. Sod should be rolled immediately after installation to remove air from under the sod.
2. Sod should be watered after installation to penetrate 300 cm (6 in.) into soil. Sod should be watered daily except in periods of intense heat or drought when frequency should be increased.
3. Contractor is responsible for first two cuttings of sod. The first cutting should be approximately 10-14 days after installation when sod is firmly established. Cutting should be on the highest level of the mower.
4. Project manager should be present for inspection at all stages of sodding.

32 93 00 Plants:

1. Tree planters for a single specimen in paved areas shall have a minimum inside dimension of 3.05 m (10 ft.). The minimum clearance from adjacent paving and structures (e.g., steps, curbs, walls, fences, and buildings) shall be 3.05 m (10 ft.) or 50% of the average mature spread for trees, and 900 mm (3 ft.) or 50% of the average mature spread for shrubs, whichever is the greater measurement. Departure from these minimum clearance requirements must have the approval of the University before installation begins.
2. Planting mixture should be 3 parts topsoil, 1-part sterilized mushroom compost, 1-part peat moss, free of weeds, roots, stones, and similar material. It should be placed in layers of not more than 150 mm at a time.
3. Installation requirements for subgrade, plant pit, planting soil mixture, root ball, mulch, finish grade around tree, staking, trunk wrap, and pruning shall be as shown in Appendix A, Figure 2.906.3-A.
4. Installation requirements for subgrade, base of plant pit, planting soil mixture, root ball, mulch, and pruning shall be as shown in Appendix A, Figure 2.906.4-A.
5. Planting should be inspected by the project manager at all stages of installation.

32 94 00 Planting Accessories**32 94 13 Landscape Edging:**

1. Where the perimeter of unit pavers abuts planting areas or where no curb edge is present, paver-edging products are required.
2. Aluminum edging system is preferred, and should have locking joining system with no obstructions, be durable, flexible, and non-rusting.

32 94 33 Precast Free-Standing Planters:

1. In general, cast-in-place planters are preferred to portable planters as the former provides better growing conditions. Corners should be rounded or chamfered; finish should be lightly textured natural (light grey).
2. Portable planters shall be precast concrete, Cylindrical Grade Adjusting Planter Type JJR by Alpha Precast, sandblasted finish. Planter size shall be 36 in. (91.4 cm) diameter and 24 in. (61.0 cm) height. Planters shall allow drainage at base.

32 94 43 Precast Tree Grates:

1. Tree grate finish, slot openings and detailing should enable barrier-free accessibility.
2. Top of tree grate shall be level with adjacent pavement. A minimum clearance of 100 mm (4 in.) is required between the bottom of the tree grate and the finish grade of soil in the tree pit.
3. Tree grate shall be precast concrete, Type TG1 (circular) and Type TG3 (square), by Alpha Precast, sandblasted finish. Tree grate size shall be 121.9 cm (4 ft.) minimum diameter or square, center hole shall be 45.7 cm (18 in.) diameter.